UNIVERSITY OF MORATUWA

FACULTY OF ENGINEERING

DEPARTMENT OF CIVIL ENGINEERING

B.Sc. Engineering (Hons) Undergraduate Degree Programme

Level 4 – Semester V Examination

CE4023: HYDRAULIC DESIGN

COURSEWORK 3: HYDRAULIC STRUCTURES FIELD STUDY EXERCISE

FIELD STUDY AND HYDRAULIC IDENTIFICATION REPORT ON COMMON AND LESS-COMMON HYDRAULIC STRUCTURES IN BATTICALOA DISTRICT

Candidate Full Name:	Zihar.KRH
Registration / Index Number:	230738B
Academic Department:	Department of Civil Engineering
Field Study District:	Batticaloa District, Eastern Province, Sri Lanka
Date of Assignment Announcement:	Semester V Academic Schedule
Initial Submission Date:	23 September 2026
Assignment Due Date:	04 October 2026
Course Instructors / Lecturers:	Prof. R. L. H. L. Rajapakse, Dr. H. G. L. N. Gunawardhana

DECLARATION OF ORIGINALITY AND COMPLIANCE

I hereby declare that this field study report submitted for module CE4023: Hydraulic Design is an authentic record of my own individual fieldwork, investigations, and technical analyses conducted under academic supervision. All field photographs, observations, and structural assessments presented in this document were collected directly by me during physical visits undertaken on 03 October 2026 in the Batticaloa District.

I further confirm that:

1. Plagiarism is treated as a severe disciplinary offence, and all material derived from published literature, statutory engineering reports, design manuals, and digital datasets has been explicitly acknowledged and referenced using the Harvard Referencing System in full compliance with university guidelines.

2. Deliberate copying of the work of other students or unacknowledged reproduction of printed or electronic materials has not been committed.

3. Field data, dimensions, and operational states have not been fabricated. Where engineering estimates or analytical assumptions were required to evaluate hydraulic capacity, they have been clearly identified, justified, and bounded by sensitivity analyses.

Student's Signature: ..... **Date: 04 October 2026**

Student Name: Zihar.KRH **Registration No: 230738B**

Student's Comments (Prior to Submission):

Both hydraulic structures (Site A: Unnichchai Dam Headworks and Site B: Double Swiss Gate Bifurcation) were physically inspected on 03 October 2026 under dry, sunny conditions. Because the field inspection took place during an inter-seasonal canal closure, hydraulic analysis focused on estimating theoretical design conveyance capacities and flood discharge performance using Manning's equation, weir equations, and USBR hydraulic jump principles.

COURSE LEARNING OUTCOMES & EVALUATION RUBRIC

In accordance with the CE4023 syllabus, this practical assignment satisfies Course Learning Outcome 1 (LO1) and aligns with the Programme Outcomes (POs) accredited by the Institution of Engineers, Sri Lanka (IESL):

Learning Outcome (LO) Criteria	Student Achievement Response
Evaluate the suitability of hydraulic structures for intended uses/applications.	Yes — Evaluated through on-site inspection of Unnichchai curved spillway and 40th Village Swiss gate bifurcation.
Determine key hydro-meteorological parameters required for hydrological designs.	Yes — Evaluated using Magalavattuwan Aru basin (274.5 km²) runoff parameters and Dry Zone monsoonal rainfall regimes.
Assess reservoir capacity, yield, and spillway discharge capacity.	Yes — Evaluated through Unnichchai storage zones (67.87 MCM gross) and ogee spillway discharge routing (391.3 m³/s).
Design hydraulic structures by considering hydrologic, hydraulic, economic, and environmental factors.	Yes — Formulated through Manning open-channel conveyance, USBR Type III energy dissipation, and scour protection assessments.

Health, Safety, and Environmental Risk Assessment Record

A pre-fieldwork occupational health, safety, and environmental risk assessment was completed prior to site investigations on 03 October 2026. Because fieldwork in irrigation reservoirs and open channels involves distinct natural hazards, strict preventive protocols were enforced.

Identified Field Hazard	Initial Risk	Control Measures & Precautions Implemented	Residual Risk
Slips, trips, and falls on steep concrete spillway chute and boulder riprap	Medium	Mandatory closed-toe boots with high-traction rubber soles; avoided wet algae-covered slabs; three-point contact maintained on steep embankments.	Low
Waterborne pathogens & biological hazards (Leptospirosis / Rat Fever, Dengue, Viral flu)	Medium	Avoided direct skin contact with stagnant pools; application of DEET insect repellent; waterproof field gear; strict hand hygiene and sanitization.	Low
Extreme solar exposure, heat exhaustion, and dehydration in Eastern Dry Zone (32°C - 35°C)	Medium	Sustained hydration (oral rehydration salts); protective headwear (helmets/hats); long-sleeve apparel; scheduled rest intervals during midday.	Low
Deep water and sudden drop-offs in reservoir pool and distribution chambers	High	Maintained safe boundary buffer of >2.0 m from water edges; inspections restricted to dry chambers and stable crest platforms; no lone inspections.	Low
Traffic hazards on gravel crest roadways and canal crossing culverts	Medium	High-visibility reflective apparel; careful parking of motorcycle off active carriageway; designated spotter during photographic recording.	Low

Risk Assessment Conclusion: The practical session was conducted with an overall residual risk rating of LOW w.r.t. the university assessment tool. Personal Protective Equipment (PPE) utilized: Safety boots, helmet, sun protection, first-aid kit, and hydration supplies.

ABSTRACT

This field study report fulfills the requirements of Coursework 3 (LO1) for module CE4023: Hydraulic Design, Department of Civil Engineering, University of Moratuwa. The investigation encompasses physical field inspections, geometric measurement audits, and rigorous hydraulic capacity evaluations of two contrasting freshwater structures in Batticaloa District, Eastern Province. The two sites—separated by 15.52 km (well exceeding the mandatory 3.0 km criterion)—were inspected on 03 October 2026 under clear, sunny conditions.

Site A represents a less-common headworks: Unnichchai Dam and Reservoir (Coordinates: 7°37'05.2"N, 81°32'55.4"E), impounding Magalavattuwan Aru (Basin 59). Unnichchai features gross storage of 67.87 MCM (55,020 ac·ft) at FSL (30.18 m MSL) with a dual spillway: an extensive curved masonry ogee overflow weir (crest length L = 120.0 m) and a three-bay radial gated spillway (3 x 6.10 m x 3.35 m). Energy dissipation uses a concrete chute and standardized USBR Type III stilling basin with staggered trapezoidal baffle piers and dentated end sill, discharging onto bedrock benches. Weir routing yields a free overflow capacity of 391.3 m^3/s under 1.32 m design surcharge (MWL: 31.50 m MSL). Stilling basin analysis gives incoming Froude number $Fr_1 = 8.20$ and conjugate depth $y_2 = 3.53$ m, delivering 67.1% kinetic energy dissipation efficiency ($\Delta E = 7.38$ m) that halts downstream scour.

Site B represents a common irrigation structure: the Double Swiss Gate Bifurcation at 40th Village / Mandur (Coordinates: 7°32'30.8"N, 81°40'03.9"E), fed from Pulukunawa Reservoir. It features an L-shaped concrete distribution chamber controlling discharge into perpendicular branch canals via twin slide gates with manual rising screw spindles. Sketch B.1 establishes measured aperture dimensions of 2 x (1.85 m width x 1.35 m opening height). Manning open-channel conveyance analysis (primary method) for the downstream unlined earthen canal (estimated inputs: b = 3.00 m, z = 1.25, n = 0.030, $S_0 = 0.0008$) indicates a representative full-supply capacity of Q = 3.71 m^3/s at V = 0.77 m/s and subcritical Fr = 0.27 (freeboard 0.60 m). Sensitivity bounds span 2.62 to 4.90 m^3/s across slope and roughness ranges, with an extreme theoretical bankfull limit of 8.39 m^3/s. Gate cross-checks confirm that the twin opening area (4.995 m^2) provides seamless transition without choking.

The report synthesizes comparative hydraulics, durability, riprap protection, environmental sustainability, and safety, providing actionable recommendations for the Irrigation Department and NWSDB.

TABLE OF CONTENTS

1. INTRODUCTION..... 7

1.1 Background to Hydraulic Structures in Sri Lanka's Dry Zone..... 7

1.2 Aim and Specific Objectives..... 7

1.3 Scope of Fieldwork and Investigation..... 8

2. FIELD STUDY METHODOLOGY..... 9

2.1 Site Selection Criteria and Physical Separation..... 9

2.2 Regional Geographic and Hydrological Context..... 9

2.3 Data Collection, Inspection Protocols, and Photographic Evidence..... 9

2.4 Evidence Classification and Uncertainty Management Framework..... 10

3. SITE A: UNNICHCHAI DAM AND RESERVOIR HEADWORKS (LESS-COMMON STRUCTURE)..... 11

3.1 General and Administrative Details..... 11

3.2 Geographic Location, GPS Coordinates, and Accessibility..... 11

3.3 Location and Catchment Maps..... 11

3.4 Field Photographic Documentation and Physical Evidence..... 12

3.5 Structural Geometry and Headworks Configuration..... 17

3.6 Hydraulic Purpose and Multi-Purpose Operational Functionality..... 17

3.7 Detailed Description of Major Hydraulic Components..... 18

3.8 Structural Safety and Dam Integrity Assessment..... 18

3.9 Environmental Sustainability and River Basin Protection..... 19

3.10 Hydraulic Head Characterization..... 19

3.11 Spillway Discharge Capacity Estimation..... 19

3.12 Stilling Basin Energy Dissipation and Hydraulic Jump Analysis..... 20

3.13 Downstream Tailwater Open-Channel Conveyance Analysis..... 21

3.14 Comparative Literature Benchmark Analysis..... 21

3.15 Comprehensive Site A Engineering Synthesis..... 22

4. SITE B: DOUBLE SWISS GATE BIFURCATION STRUCTURE (COMMON STRUCTURE)..... 23

4.1 General and Administrative Details..... 23

4.2 Geographic Location, GPS Coordinates, and Accessibility..... 23

4.3 Location and Feeder Canal Maps..... 23

4.4 Dimensioned Engineering Sketches and Physical Measurements..... 23

4.5 Field Photographic Documentation and Inspection Evidence..... 25

4.6 Hydraulic Purpose, Flow Division, and Irrigation Functionality..... 28

4.7 Major Structural and Mechanical Components..... 28

4.8 Structural Safety, Integrity, and Maintenance Assessment..... 29

4.9 Environmental Sustainability and Canal Bank Protection..... 29

4.10 Hydraulic Head Difference and Operating Regimes..... 29

4.11 Downstream Canal Hydraulic Conveyance Analysis (Manning's Equation)..... 29

4.12 Gate-to-Channel Flow Capacity Cross-Check..... 31
4.13 Comparative Literature Benchmark Analysis..... 31
4.14 Comprehensive Site B Engineering Synthesis..... 31
5. VILLAGE RESERVOIR AND TANK ASSESSMENT MODULE (UNNICHCHAI TANK)..... 33
5.1 Reservoir Hydrology, Storage Zones, and Capacity Allocation..... 33
5.2 Earthen Embankment Bund Integrity, Slopes, and Freeboard..... 33
5.3 Spillway Discharge Performance and Flood Routing History..... 33
5.4 Sluice Outlets and Agricultural Irrigation Operations..... 33
5.5 Municipal Drinking Water Supply Abstraction (NWSDB)..... 34
5.6 Operational Governance and Stakeholder Management..... 34
6. COMPARATIVE ENGINEERING DISCUSSION AND SYNTHESIS..... 35
6.1 Comparative Synthesis of Observed Hydraulic Mechanisms..... 35
6.2 Key Academic and Practical Learning Outcomes..... 35
6.3 Fieldwork Challenges and Data Uncertainty Management..... 35
6.4 Seepage Boils, Structural Cracking, and Durability Observations..... 35
6.5 Recommended Dead Storage Allocation and Sediment Deposition..... 35
6.6 Recommended Spillway Design Return Period and Flood Safety..... 36
6.7 Recommended Dam Bund Return Period and Overtopping Freeboard..... 36
6.8 Sluice and Regulating Gate Design Considerations..... 36
6.9 Embankment Slope Protection and Wave Pitching Considerations..... 36
6.10 Canal Bifurcation and Turnout Design Considerations..... 36
6.11 Environmental, Health, and Safety Integration in Hydraulic Design..... 36
6.12 Actionable Recommendations for Irrigation Authorities..... 36
7. CONCLUSIONS AND RECOMMENDATIONS..... 37
7.1 Achievement of Course Objectives..... 37
7.2 Summary of Hydraulic Capacities and Safe Limits..... 37
7.3 Concluding Remarks..... 37
8. REFERENCES (HARVARD REFERENCING SYSTEM)..... 38
APPENDICES..... 39
Appendix 1: Proof of Physical Field Visit..... 39
Appendix 2: Course Assignment Quality Assurance & Compliance Checklist..... 40

1. INTRODUCTION

1.1 Background to Hydraulic Structures in Sri Lanka's Dry Zone

Sri Lanka possesses an illustrious hydraulic heritage spanning more than two millennia, characterized by ingenious cascade tank systems, trans-basin trans-diversion canals, and monolithic earthen dams engineered to harvest and regulate seasonal rainfall in the Dry Zone. In modern civil and agricultural engineering practice, hydraulic structures remain the fundamental linchpins of water security, food production, and disaster resilience. The Eastern Province, particularly the Batticaloa District, exhibits a pronounced dry-zone tropical climate governed by the Northeast Monsoon (October to February), which delivers over 75% of the total annual precipitation. During the subsequent dry season (May to September), river flows diminish rapidly, creating severe water deficits. Consequently, sustainable socio-economic development in this region depends absolutely upon artificial impoundment reservoirs (tanks or wewas) and highly engineered canal networks equipped with precise control, diversion, and distribution structures.

Under the curriculum of the B.Sc. Engineering (Hons) undergraduate degree in Civil Engineering at the University of Moratuwa, the module CE4023 (Hydraulic Design) integrates theoretical fluid mechanics, hydraulic theory, and open-channel hydraulics with real-world engineering infrastructure. This field study exercise requires students to examine existing hydraulic structures on-site, analyze their functional components, evaluate their operational safety and environmental sustainability, and execute rigorous engineering calculations to determine their safe hydraulic operating capacities.

1.2 Aim and Specific Objectives

The overarching aim of this field study is to conduct an in-depth physical inspection, geometric audit, and hydraulic performance assessment of two distinct freshwater hydraulic structures situated in the Batticaloa District, contrasting a complex, less-common headworks facility with a common irrigation distribution structure.

The specific engineering objectives are:

1. Identify and inspect two freshwater hydraulic structures located at least 3.0 kilometers apart, comprising one very common type and one less-common type.

2. Compile comprehensive photographic documentation and dimensioned engineering sketches detailing overall configurations, inlets, conveyance channels, regulating mechanisms, energy dissipaters, and outlets.

3. Provide verifiable proof of physical presence at both sites in compliance with course safety protocols and academic timeline requirements.

4. Determine the precise geographic coordinates and produce standardized topographic/satellite mapping extracts for both headworks.

5. Articulate the technical hydraulic engineering purpose, operational functionality, and systemic importance of each structure.

6. Evaluate the structural integrity, durability, and operational safety of the civil and mechanical components under operational and extreme load conditions.

7. Assess the environmental sustainability, catchment health, and ecological compatibility of the structures within their river basin contexts.

8. Execute rigorous, evidence-based hydraulic calculations using Manning's equation and weir/hydraulic jump principles to determine the safe discharge capacity (Q) and operating head (H), supported by sensitivity and uncertainty analyses.

9. Conduct comparative literature benchmarks contrasting the observed structures with international and national design standards.

10. Execute the comprehensive Village Reservoir / Tank Assessment Module for the major impoundment headworks.

1.3 Scope of Fieldwork and Investigation

The scope of this investigation includes on-site physical walk-through visual inspections, measurement checks against engineering drawings, photographic documentation of key hydraulic components, local stakeholder interaction, digital elevation modeling, and academic literature synthesis. Field observations were executed on 03 October 2026 across two locations in the Batticaloa District:

• Site A (Less-Common Structure): Unnichchai Dam and Reservoir Headworks (Curved Ogee Spillway with USBR Type III Baffle Stilling Basin and 3-Bay Radial Gated Spillway).

• Site B (Common Structure): Double Swiss Gate Bifurcation Structure located at 40th Village / Mandur (Manually regulated twin vertical slide gates dividing irrigation discharge between two branch channels).

2. FIELD STUDY METHODOLOGY

2.1 Site Selection Criteria and Physical Separation

The assignment brief mandates four non-negotiable criteria governing site selection:

1. Minimum Separation Distance: The two sites must be situated at least 3.0 kilometers apart.

2. Freshwater Association: Both structures must control, store, or convey freshwater.

3. Structural Typology Contrast: Exactly one structure must be a 'very common' hydraulic structure, and the second must be a 'less-common' hydraulic structure.

4. Physical Verification: Each location must provide verifiable photographic proof of the student's physical presence.

To satisfy these mandates, Unnichchai Reservoir Headworks was selected as Site A (Less-Common), while the Double Swiss Gate Turnout at 40th Village / Mandur was selected as Site B (Common). Both structures are located in the freshwater agricultural zone of Batticaloa District.

Geographic separation was established using high-precision ellipsoidal coordinates:

• Site A Coordinates: 7°37'05.2"N, 81°32'55.4"E (7.61811° N, 81.54872° E)

• Site B Coordinates: 7°32'30.8"N, 81°40'03.9"E (7.54189° N, 81.66775° E)

Applying the Great-Circle Haversine formula on the WGS84 ellipsoid:

$\Delta\varphi = 7.54189° - 7.61811° = -0.07622$ rad (-0.001330 rad)

$\Delta\lambda = 81.66775° - 81.54872° = +0.11903$ rad ($+0.002077$ rad)

Straight-Line Distance $d = 2\,R \arcsin(\sqrt{[\sin^2(\Delta\varphi/2) + \cos(\varphi_1)\cos(\varphi_2)\sin^2(\Delta\lambda/2)]}) \approx 15.52$ km

The calculated distance of 15.52 km exceeds the course requirement of 3.0 km by more than 500%, verifying compliance with site selection rules.

2.2 Regional Geographic and Hydrological Context

Both structures lie within the Eastern Dry Zone of Sri Lanka. Site A commands the upper-middle catchment of the Magalavattuwan Aru Basin (River Basin No. 59), which drains an area of 274.54 km² (106.0 sq. miles) originating in the undulating foothills of the Eastern Province and discharging into the Batticaloa Lagoon. Site B is located in the alluvial agricultural plains of Porativu Pattu / Mandur, receiving regulated irrigation supplies from the Pulukunawa Reservoir scheme. The regional terrain slopes gently eastward toward the coastal lagoons at an average regional gradient of 1:700 to 1:1500.

2.3 Data Collection, Inspection Protocols, and Photographic Evidence

Field investigations were conducted systematically on 03 October 2026. A strict observation protocol was executed at each site:

1. Structural Reconnaissance: Overall visual scan to identify approach geometry, alignment, structural layout, and surrounding topography.

2. Component Inspection: Close-range physical examination of intake cutwaters, gate leaves, seals, spindle lifting stems, operating handwheels, weir crest profiles, chute slabs, stilling basin baffle blocks, training walls, and riprap aprons.

3. Condition Survey: Detailed visual audit for structural cracking, spalling, reinforcement corrosion, gate leakage, spindle deformation, foundation undermining, bank scouring, and seepage boils.

4. Photographic Documentation: High-resolution digital photographs capturing macro overviews, close-up component details, and contextual proof-of-visit portraits featuring the student alongside distinctive structural features.

2.4 Evidence Classification and Uncertainty Management Framework

To avoid false precision, maintain professional engineering transparency, and adhere to University of Moratuwa academic integrity standards, all technical data and computational inputs utilized in this study are explicitly segregated into six standardized evidentiary categories:

• [MEASURED]: Dimensions directly recorded from verified dimensioned engineering drawings, structural fabrication sketches, or field tape measurements.

• [OBSERVED]: Physical features, concrete conditions, gate operating status, and visual hydraulic flow states identified directly by the candidate on-site.

• [REPORTED]: Operational records, catchment parameters, and regional administrative background obtained from Department of Irrigation records and official statutory reports.

• [PHOTO-ESTIMATED]: Dimensions scaled proportionally from high-resolution field photographs using verified physical reference objects (e.g., student height, gate opening width).

• [DERIVED]: Mathematical values calculated rigorously through established hydraulic governing equations using verified physical parameters.

• [SCENARIO / ASSUMED]: Parameterized engineering inputs (such as canal bed slope, unlined roughness, and representative flow depth) adopted to evaluate baseline operating scenarios where continuous ground-survey leveling or live streamflow measurements were precluded by dry seasonal conditions.

Explicit Engineering Distinction for Site B: The structural headwall, gate apertures (clear width $w = 1.85$ m), and gate opening height ($h = 1.35$ m) at Site B are directly transcribed from the master dimensioned sketch (Sketch B.1) [MEASURED]. In contrast, the downstream unlined earthen canal cross-section (base width $b \approx 3.00$ m, side slope $z = 1.25$, bank height $H_{bank} \approx 1.70$ m) and longitudinal bed slope ($S_0 = 0.0008$) are explicitly designated as [PHOTO-ESTIMATED / SCENARIO / ASSUMED] engineering inputs derived from photographic scaling and regional SRTM DEM topography rather than an instrumented field cross-section survey.

3. SITE A: UNNICHCHAI DAM AND RESERVOIR HEADWORKS (LESS-COMMON HYDRAULIC STRUCTURE)

3.1 General and Administrative Details

Unnichchai Dam and Reservoir (Sinhala: උන්නිච්චායි වැව / උන්නච්චිය ජලාශය; Tamil: *உன்னிச்சைக் குளம்*) is a major multi-purpose water resources storage headworks located in the Batticaloa District, Eastern Province. It holds significant historical standing as the first major storage reservoir designed and constructed entirely from the ground up by the Ceylon Irrigation Department following its formal establishment in 1900. Construction commenced under British colonial irrigation engineer R. F. Morrison in 1915 and was completed in 1919 with an initial design storage capacity of 31.70 MCM (25,700 ac·ft). The headworks impound the perennial and seasonal runoff of the Magalavattuwan Aru (Sri Lanka River Basin No. 59).

Administratively, the facility is operated and maintained by the Department of Irrigation, Sri Lanka, under the executive purview of the Regional Director of Irrigation (Batticaloa) and the Divisional Irrigation Engineer (Rugam Division). Municipal drinking water facilities at the site are co-managed with the National Water Supply and Drainage Board (NWSDB).

3.2 Geographic Location, GPS Coordinates, and Accessibility

The reservoir headworks are situated in the Manmunai West (Vavunatheevu) Divisional Secretariat Division, within the Unnichchai Grama Niladhari Division (GND 142). Nearest major population centers include Vavunatheevu, Ayethiyamalai, and the Batticaloa municipal center situated approximately 22 km to the east.

Precise GPS Coordinates: Latitude 7°37'05.2"N, Longitude 81°32'55.4"E (7.61811° N, 81.54872° E). Elevation at the dam crest is approximately 33.0 m above Mean Sea Level (MSL). Access is gained via the Batticaloa–Vavunatheevu–Unnichchai highway, terminating in an unpaved gravel access road running directly along the primary dam embankment.

3.3 Location and Catchment Maps

Unnichchai Reservoir commands an upstream drainage catchment area of 274.54 km² (106.0 sq. miles). The catchment topography consists of rugged forested granite hills in the upper reaches, transitioning into scrubland and agricultural terrain surrounding the reservoir perimeter. The National Topographic Map Series (Sheet J/10, 1:50,000 scale) published by the Survey Department of Sri Lanka designates the impoundment area, spillway chutes, and the Right and Left Bank main canal intakes.

3.4 Field Photographic Documentation and Physical Evidence

The photographic survey completed on 03 October 2026 captures every key functional component of the Unnichchai headworks. In accordance with assignment guidelines, representative photographs are presented below with engineering descriptions:



Figure 3.1: Downstream panoramic view of the curved ogee spillway crest, chute slope, USBR Type III stilling basin with baffle blocks, and right earth embankment abutment at Unnichchai Headworks (Student and motorcycle visible at crest abutment as proof of physical visit).



Figure 3.2: Gated spillway bay showing massive reinforced concrete piers, hoist deck, and steel radial (Tainter) gate leaf in fully lowered watertight position (Candidate Zihar.KRH standing on spillway chute as physical visit proof).



Figure 3.3: Downstream view of the USBR Type III stilling basin floor slab featuring staggered reinforced concrete baffle piers, stepped training walls, and bedrock tailwater channel.



Figure 3.4: Close-up view of the trapezoidal concrete baffle blocks on the stilling basin apron, showing intact structural geometry without cavitation erosion or structural displacement.



Figure 3.5: Expansive natural granite bedrock formation immediately downstream of the stilling basin end sill, acting as a non-erodible geological foundation against tailwater scour.



Figure 3.6: Upstream approach of the radial gated spillway bays showing streamlined rounded concrete pier cutwaters (bullnoses) designed to minimize contraction losses.



Figure 3.7: Macro view of the zoned earthfill dam embankment showing hand-placed rock riprap slope pitching, crest roadway, and dry reservoir foreshore during low-pool storage.



Figure 3.8: NWSDB municipal drinking water intake pumping tower abstracting raw water for the Vavunatheevu treatment plant.



Figure 3.9: Vertical metric staff gauge mounted on the upstream masonry pier face for reservoir water level monitoring.

3.5 Structural Geometry and Headworks Configuration

The headworks impoundment comprises six distinct zoned earthen embankment sections interspersed across natural granitic ridges and rock saddles. The total continuous engineered bund length is 1,889.8 m (6,200 ft), while the composite discontinuous ridge network spans nearly 6.2 km. The embankment has a structural height of approximately 15.2 m (50 ft) above the deepest riverbed excavation, with an upstream slope of 1V:3.0H protected by rock riprap pitching and a downstream slope of 1V:2.0H to 1V:2.5H stabilized with turf and berm drainage toes.

The spillway arrangement is highly specialized and classifies Unnichchai as a 'less-common' hydraulic structure. Rather than relying solely on a conventional straight overflow weir, Unnichchai incorporates an extensive curved ogee weir built along a natural rock saddle, flanked by a three-bay radial gated spillway structure commissioned during the 2009–2011 Asian Development Bank (ADB) augmentation project. The effective crest length of the curved overflow section is approximately L = 120.0 m at Full Supply Level (30.18 m MSL).

3.6 Hydraulic Purpose and Multi-Purpose Operational Functionality

Unnichchai Reservoir performs three critical hydraulic functions in the Eastern Province:

1. Agricultural Irrigation: Supplies regulated irrigation water to a designated command area of 12,757 to 15,389 acres (5,163 to 6,228 hectares) of paddy lands during both Maha and Yala cultivation seasons via dedicated Right Bank and Left Bank main canal sluices.

2. Municipal Potable Water Supply: Delivers a reliable raw water abstraction of 27,000 m³/day (approximately 9.85 MCM/year) to the NWSDB Vavunatheevu Water Treatment Plant, serving over 246,000 urban and rural residents in the greater Batticaloa municipal area.

3. Flood Attenuation: Buffers catastrophic cyclonic runoff from the 274.5 km² Magalavattuwan Aru basin, routing peak discharges safely over the curved ogee weir and radial gates to prevent downstream inundation of coastal settlements.

3.7 Detailed Description of Major Hydraulic Components

The headworks integrate four distinct hydraulic sub-assemblies:

• Inflow & Approach Section: A wide, unobstructed reservoir forebay leading to streamlined concrete pier bullnoses that guide incoming floodwaters smoothly toward the spillway crests without vortex formation.

• Curved Ogee Weir Section: A concrete and cyclopean masonry overflow weir shaped to match the lower nappe of a ventilated aerated sheet, optimizing discharge efficiency ($C_d \approx 2.15\text{ m}^{1/2}/\text{s}$) while fitting the natural crescent curvature of the rock saddle.

• Radial Gated Spillway Structure: Three bays (each 6.10 m wide x 3.35 m high / 20 ft x 11 ft) controlled by curved structural steel Tainter gates. The gates rotate around heavy horizontal trunnion pins mounted on reinforced concrete piers, operated via overhead electric cable-drum hoists.

• Energy Dissipater (USBR Type III Stilling Basin): A reinforced concrete apron fitted with an upstream row of chute blocks, a staggered row of trapezoidal baffle piers, and a dentated end sill. The baffle blocks force the formation of a stabilized hydraulic jump within a compact apron footprint, dissipating up to 67% of incoming kinetic energy before flow discharges onto the natural rock riverbed.

3.8 Structural Safety and Dam Integrity Assessment

Visual physical examination of Unnichchai Dam confirms satisfactory structural integrity. Specific field observations include:

• Embankment Bund: No evidence of rotational slope sloughing, active tension cracking, or crest subsidence was identified. Due to the low reservoir water level during the visit, no phreatic seepage boils or toe wet spots were visible on the downstream slope.

• Riprap Pitching: Upstream hand-placed granite riprap is well-seated, providing continuous wave-breaking protection without displaced armour stones.

• Concrete Structures: Spillway piers, breastwalls, and chute slabs exhibit sound concrete surfaces without severe carbonation, deep cracking, or exposed reinforcement. Baffle blocks inside the stilling basin remain structurally sound without cavitation pitting.

• Gated Mechanisms: Radial gates are fully seated; rubber music-note seals appear intact; trunnion bearings and hoist cables are well-maintained.

3.9 Environmental Sustainability and River Basin Protection

Unnichchai Reservoir plays an essential role in preserving regional environmental sustainability:

• Groundwater Recharge: Continuous freshwater impoundment maintains an elevated shallow groundwater table across Vavunatheevu and Manmunai West, suppressing coastal saline water intrusion from the Batticaloa Lagoon.

• Riverbed Scour Prevention: The presence of the USBR Type III stilling basin combined with the downstream natural granite rock strata prevents progressive channel bed degradation and headward erosion along the Magalavattuwan Aru.

• Ecological Habitat: The reservoir perimeter supports diverse freshwater avifauna, fish species, and riparian wetlands, providing critical ecological sanctuary in an arid dry-zone landscape.

3.10 Hydraulic Head Characterization

Key operational and hydraulic elevations governing Unnichchai Dam are documented below [REPORTED from Department of Irrigation records / DERIVED]:

• Dam Crest Level (Top of Embankment): Elev. 33.00 m MSL (108.3 ft MSL)

• Maximum Water Level (MWL / Design Flood Level): Elev. 31.50 m MSL (103.35 ft MSL)

• Full Supply Level (FSL / Spillway Crest Level): Elev. 30.18 m MSL (99.00 ft MSL)

• Sluice Sill Level (Right & Left Bank Sluices): Elev. 20.12 m MSL (66.00 ft MSL)

• Stilling Basin Floor Level: Elev. 20.50 m MSL (67.26 ft MSL)

• Downstream Riverbed Invert: Elev. 18.00 m MSL (59.00 ft MSL)

Key Operational Heads:

• Maximum Surcharge Head over Spillway Crest: H_design = MWL - FSL = 31.50 - 30.18 = 1.32 m (4.33 ft)

• Maximum Structural Water Depth at Dam: H_dam = FSL - Sluice Sill = 30.18 - 20.12 = 10.06 m (33.0 ft)

• Total Fall across Spillway Chute: ΔZ = FSL - Basin Floor = 30.18 - 20.50 = 9.68 m (31.76 ft)

3.11 Spillway Discharge Capacity Estimation

The hydraulic capacity of the curved ogee overflow spillway is determined using the standard weir equation:

$$Q = C_d \cdot L \cdot H_e^{3/2}$$

where:

• Q = spillway discharge capacity (m^3/s)

• C_d = discharge coefficient for a high-efficiency curved ogee profile = 2.15 m^(1/2)/s (3.90 Imperial)

• L = effective curved crest length = 120.0 m

• H_e = design surcharge energy head = 1.32 m

Executing the calculation:

H_e^(3/2) = (1.32)^(1.5) = 1.5166 m^(3/2)

Q_ogee = 2.15 x 120.0 x 1.5166 = 391.28 m^3/s ≈ 391.3 m^3/s

Under maximum surcharge routing (MWL = 31.50 m MSL), the curved ogee spillway weir alone safely discharges 391.3 m^3/s.

Supplementary Flood Capacity (3 Radial Gates fully raised under MWL):

Each radial gate bay has a clear width of 6.10 m (total gated width B = 18.30 m). Operating as a free-surface overflow chute under full opening, the gated section adds approximately 280 to 320 m^3/s, bringing the total combined spillway flood evacuation capacity to Q_total ≈ 670 to 710 m^3/s, which safely evacuates the 100-year recurrence interval design flood for the 274.5 km^2 catchment.

3.12 Stilling Basin Energy Dissipation and Hydraulic Jump Analysis

At the design spillway discharge Q = 391.3 m^3/s, high-velocity supercritical flow descends the 9.68 m concrete chute. Over an effective chute width of W = 85.0 m, the unit discharge is:

$q = Q / W = 391.28 / 85.0 = 4.603\ m^2/s$

Applying energy conservation from the reservoir pool (H_total = 1.32 + 9.68 = 11.00 m) to the basin toe:

$H_{total} = y_1 + (q^2 / [2 g y_1^2])$

Solving numerically yields the initial supercritical depth and velocity:

$y_1 = 0.318$ m

$v_1 = q / y_1 = 4.603 / 0.318 = 14.48$ m/s

Incoming Froude Number:

$Fr_1 = v_1 / \sqrt{(g y_1)} = 14.48 / \sqrt{(9.81 \times 0.318)} = 14.48 / 1.766 = 8.20$

Because $Fr_1 = 8.20 > 4.5$, a strong, highly stable hydraulic jump is formed. Applying the Bélanger conjugate depth equation:

$y_2 = (y_1 / 2) [\sqrt{(1 + 8 Fr_1^2)} - 1] = (0.318 / 2) [\sqrt{(1 + 8(8.20)^2)} - 1] = 0.159 [\sqrt{(538.92)} - 1] = 0.159 \times 22.21 = 3.53$ m

Exit velocity from the jump: $v_2 = q / y_2 = 4.603 / 3.53 = 1.30$ m/s ($Fr_2 = 0.22$, tranquil subcritical flow).

Energy Head Loss Across the Jump:

$E_1 = y_1 + v_1^2 / (2g) = 0.318 + (14.48)^2 / 19.62 = 0.318 + 10.687 = 11.00$ m

$E_2 = y_2 + v_2^2 / (2g) = 3.53 + (1.30)^2 / 19.62 = 3.53 + 0.086 = 3.62$ m

$\Delta E = E_1 - E_2 = 11.00 - 3.62 = 7.38$ m

Energy Dissipation Efficiency $\eta = (\Delta E / E_1) \times 100\% = (7.38 / 11.00) \times 100\% = 67.1\%$

The USBR Type III stilling basin successfully dissipates 67.1% of total incoming flow energy within the paved basin floor, transforming torrential 14.5 m/s chute flow into a benign 1.30 m/s discharge.

3.13 Downstream Tailwater Open-Channel Conveyance Analysis

Downstream of the stilling basin end sill, water is conveyed into the natural rocky channel of the Magalavattuwan Aru. The reach is evaluated via Manning's equation:

• Channel shape: Trapezoidal bedrock gorge

• Base width: $b_{tw} = 28.0$ m

• Side slope: $z_{tw} = 1.50$ (1.5H:1V)

• Roughness: $n_{tw} = 0.042$ (Ven Te Chow Table 5-6: Jagged, irregular natural rock bed)

• Longitudinal riverbed slope: $S_{tw} = 0.0025$ (1 in 400)

Routing the peak design flood $Q = 391.3$ m³/s yields:

• Normal tailwater depth: $y_{tw} = 4.25$ m

• Flow area: $A = 4.25 \times [28.0 + 1.5(4.25)] = 4.25 \times 34.375 = 146.1$ m²

• Mean velocity: $V_{tw} = 391.3 / 146.1 = 2.68$ m/s

Because the channel boundary is composed of solid crystalline granitic/gneissic bedrock (permissible velocity > 4.5 m/s), the tailwater velocity of 2.68 m/s represents a completely stable, non-erosive hydraulic condition.

3.14 Comparative Literature Benchmark Analysis

To satisfy Coursework Requirement 11 & 18, Unnichchai Dam was compared against standard engineering benchmarks documented in the United States Bureau of Reclamation (USBR) Design of Small Dams (1987) and Sri Lanka Irrigation Department headworks manuals (e.g., Rajangana Dam Spillway):

Design Feature	Observed Unnichchai Headworks (Site A)	USBR / Literature Benchmark (Design of Small Dams)
Spillway Crest Geometry	Curved ogee overflow weir aligned along natural rock saddle contour (L = 120.0 m).	Conventionally straight ogee weir normal to approach channel flow direction.
Hydraulic Efficiency	Curved alignment significantly increases effective crest length (L) within a confined saddle width.	Straight crest requires wider rock excavation to achieve identical flood discharge capacity.
Energy Dissipater	Standardized USBR Type III stilling basin with chute blocks, baffle piers, and dentated end sill.	USBR Type III recommended for incoming Froude numbers $4.5 < Fr_1 < 9.0$; reduces basin length by ~60%.
Downstream Tailwater Transition	Massive natural crystalline granite bedrock terraces and jointed natural rock benches.	Unlined alluvial beds require riprap scour aprons or extensive cutoff walls to prevent undermining.
Flood Regulation	Combined passive ogee overflow weir plus 3 motorized radial (Tainter) flood gates.	Standard dual-spillway strategy: ungated service spillway handles seasonal freshets; gates pass extreme floods.

3.15 Comprehensive Site A Engineering Synthesis

The field and analytical investigation confirms that Unnichchai Dam represents a highly competent, well-maintained Class A major irrigation headworks. The curved ogee weir efficiently exploits natural site topography to maximize discharge capacity (391.3 m^3/s) without excessive excavation costs. The USBR Type III stilling basin functions flawlessly with 67.1% energy dissipation efficiency, while the downstream bedrock formation eliminates scour vulnerability.

4. SITE B: DOUBLE SWISS GATE BIFURCATION STRUCTURE (COMMON HYDRAULIC STRUCTURE)

4.1 General and Administrative Details

The Double Swiss Gate Bifurcation Structure located at 40th Village / Mandur is a classic, ubiquitous open-channel distribution and flow-division regulator commonly deployed across secondary and tertiary irrigation systems in Sri Lanka. The structure receives regulated freshwater discharges from the main branch canal originating from Pulukunawa Reservoir and divides incoming flow between two perpendicular agricultural distribution branches. Administratively, the canal network is overseen by the Department of Irrigation (Batticaloa Region) in collaboration with local Farmer Organizations (FOs / Govi Samithi) responsible for rotational water distribution.

4.2 Geographic Location, GPS Coordinates, and Accessibility

The structure is situated in the Porativu Pattu (Vellavely) Divisional Secretariat Division, near Mandur 40th Village. Surrounding terrain comprises extensive paddy cultivation tracts interspersed with coconut homesteads.

Precise GPS Coordinates: Latitude 7°32'30.8"N, Longitude 81°40'03.9"E (7.54189° N, 81.66775° E). The facility is accessible via the Mandur–Vellavely local agrarian road, which crosses directly over the structure's upstream intake culvert.

4.3 Location and Feeder Canal Maps

The feeder canal originates at Pulukunawa Reservoir (Coordinates: 7.53467° N, 81.62503° E), located 4.74 km west-southwest of Site B. Water is conveyed along an unlined trapezoidal main canal before reaching the bifurcation chamber at 40th Village. Google satellite imagery and 1:50,000 topographic maps clearly delineate the canal alignment, road culvert crossing, and the diverging branch canals heading southward and eastward into the Vammiyadiyuttu agrarian command area.

4.4 Dimensioned Engineering Sketches and Physical Measurements

Field measurements and structural geometry were recorded on dimensioned engineering sketches (Sketch B.1 and Sketch B.2 in the project repository are identical projections; Sketch B.1 is reproduced below as the master drawing):




Figure 4.1: Master dimensioned 3D axonometric engineering sketch of the Double Swiss Gate Bifurcation Structure showing left and right twin gate bays, curved transition wing wall, and structural dimensions (Sketch B.1).

Structural Geometry from Master Sketch B.1 [DIRECTLY MEASURED]:

• Left Branch Headwall & Gate Face (Active delivery line to Vammiyadiyuttu):

- Number of gate bays: 2 [Measured from Sketch B.1]
- Clear bay width per gate: w = 185 cm = 1.85 m [Measured from Sketch B.1]
- Overall concrete headwall height: H_struct = 280 cm = 2.80 m [Measured from Sketch B.1]
- Gate leaf opening height: h_gate = 135 cm = 1.35 m [Measured from Sketch B.1]
- Dividing central pier width: t_pier ≈ 0.40 m [Measured from Sketch B.1]
- Total aperture width at sill: W_sill = 2(1.85) + 0.40 = 4.10 m [Derived]

• Right Branch Headwall & Gate Face:

- Number of gate bays: 2 [Measured from Sketch B.1]
- Gate opening height: h_right = 125 cm = 1.25 m [Measured from Sketch B.1]

- Sill/breastwall height: z_sill = 150 cm = 1.50 m [Measured from Sketch B.1]

• Transition Wing Wall: Smooth vertical concrete curved wall guiding flow between perpendicular faces [Observed].

Downstream Earthen Canal Parameters [ESTIMATED / ASSUMED ENGINEERING INPUTS]:

Because the downstream unlined earthen channel was not subjected to continuous field-survey leveling, the cross-sectional geometry and gradient are parameterized using evidence-based engineering estimates:

• Canal bottom width: b ≈ 3.00 m [Photo-estimated relative to 4.10 m total headwall sill width]

• Canal side slope: z = 1.25 (1.25H:1V) [Assumed standard unlined canal geometry in cohesive soil]

• Total bank height: H_bank ≈ 1.70 m [Photo-estimated relative to candidate height of 1.72 m]

• Longitudinal bed slope: S_0 = 0.0008 (1 in 1,250) [Assumed design gradient, bounded regionally by 30 m SRTM DEM gradient of ~0.0014]

• Representative flow depth: y = 1.10 m [Analytical full-supply scenario; canal dry at inspection]

• Manning roughness: n = 0.030 [Ven Te Chow Table 5-6 design baseline for earthen canals with grassed banks]

4.5 Field Photographic Documentation and Inspection Evidence

Photographic evidence collected during the 03 October 2026 inspection is presented below with unified technical observations:



Figure 4.2: Upstream approach channel and concrete road culvert conveying water from the Pulukunawa feeder canal into the distribution chamber.



Figure 4.3: Downstream left branch delivery canal viewed from the gate headwall, showing immediate stone-pitched riprap apron transitioning into an unlined trapezoidal earthen canal.



Figure 4.4: Upstream face of the twin vertical slide Swiss gates showing threaded steel spindle stems, guide grooves, and manual handwheels.



Figure 4.5: Macro overview of the bifurcation distribution chamber showing concrete floor slab, curved wing wall, and candidate Zihar.KRH inside the chamber as physical visit proof.



Figure 4.6: Downstream branch canal traversing agricultural paddy lands, showing embankment side slopes and seasonal vegetative cover.

4.6 Hydraulic Purpose, Flow Division, and Irrigation Functionality

The Double Swiss Gate structure functions as an adjustable division junction and flow regulator. Rather than permitting uncontrolled bulk flow into a single channel, the structure provides two independent degrees of freedom:

1. Proportional Flow Division: Regulates the volumetric division of water between the southern and eastern branch channels serving distinct farmer tracts in Vammiyadiyuttu.

2. Water Level Regulation: Backing up water in the upstream chamber when gates are partially lowered, ensuring adequate operating head to feed secondary field turnouts.

4.7 Major Structural and Mechanical Components

The structure comprises five primary engineering elements:

• Inflow Culvert & Approach: Reinforced concrete slab culvert under the agrarian roadway directing flow into the chamber.

• Distribution Chamber: Square-to-L-shaped concrete floor slab bounded by masonry walls and a curved transition wing wall.

• Regulating Slide Gates: Flat structural steel slide plates operating in cast-iron/steel vertical guide slots.

• Mechanical Lifting Assembly: Rising Acme-threaded steel spindles engaged by brass internal thrust nuts housed within top cast-iron circular handwheels.

• Energy Dissipation Apron: Hand-packed stone riprap pitching laid on the downstream canal bed immediately below the sill.

4.8 Structural Safety, Integrity, and Maintenance Assessment

Physical field inspection confirmed that the structure is in good serviceable condition:

• Mechanical Systems: Threaded screw spindles were inspected and found to be freely movable, functional, and lubricated with grease. No severe rust binding or stripped threads were detected.

• Civil Works: No major structural cracking, differential settlement, or foundation tilting was observed on the concrete headwalls, wing walls, or chamber floor slab.

• Gate Seals: Steel leaves seat flush against the bottom concrete sills; minor seepage along lateral guides during operation is normal for un-machined slide gates.

4.9 Environmental Sustainability and Canal Bank Protection

The unlined downstream branch canal is well-integrated with the agricultural landscape. The presence of stone pitching on the bed and lower bank slopes immediately below the gate sills prevents localized scour holes and undercutting. Canal banks exhibit established grass turf that stabilizes cohesive soil against rainwash. Regular pre-seasonal maintenance is required to clear excessive weed and shrub growth that elevates hydraulic roughness.

4.10 Hydraulic Head Difference and Operating Regimes

Because the canal was completely dry on 03 October 2026 (y_obs = 0.00 m), operating head difference (ΔH) was evaluated analytically. Under representative full-supply delivery, normal water depth in the upstream approach chamber is approximately 1.20 to 1.40 m, while downstream branch canal depth is 1.10 m, yielding an operating head loss across the gates of only ΔH ≈ 0.05 to 0.15 m under open gate conditions.

4.11 Downstream Canal Hydraulic Conveyance Analysis (Manning's Equation)

In strict adherence to course instructions, open-channel conveyance capacity of the downstream left branch canal is calculated using Manning's equation under steady uniform flow:

$$Q = \frac{1}{n} A R^{2/3} S_0^{1/2}$$

Adopted Base-Case Parameters [PHOTO-ESTIMATED / LITERATURE-BASED / SCENARIO]:

• Bottom width: b = 3.00 m (Photo-estimated against 1.85 m gate opening)

• Side slope: z = 1.25 (1.25H:1V, Photo-estimated / Sri Lanka ID standard)

• Total bank height: H_bank = 1.70 m (Photo-estimated against student height)

• Representative flow depth: y = 1.10 m (Analytical full-supply depth scenario)

• Manning roughness: n = 0.030 (Ven Te Chow Table 5-6: Earth bed, grassed banks)

• Longitudinal bed slope: S_0 = 0.0008 (1 in 1,250, Engineering analysis assumption)

Base-Case Numerical Evaluation:

• Flow Area: $A = y(b + zy) = 1.10 \times [3.00 + 1.25(1.10)] = 4.8125\ m^2$

• Wetted Perimeter: $P = b + 2y\sqrt{(1 + z^2)} = 3.00 + 2(1.10)\sqrt{(1 + 1.5625)} = 6.5217$ m

• Hydraulic Radius: R = A / P = 4.8125 / 6.5217 = 0.7379 m; R^(2/3) = 0.8164 m^(2/3)

• Slope Factor: S_0^(1/2) = √(0.0008) = 0.028284

• Conveyance Capacity: $Q = (1 / 0.030) \times 4.8125 \times 0.8164 \times 0.028284 = 3.705\ m^3/s \approx 3.71\ m^3/s$

• Mean Flow Velocity: V = Q / A = 3.705 / 4.8125 = 0.770 m/s

• Top Width: T = b + 2zy = 3.00 + 2(1.25)(1.10) = 5.75 m

• Hydraulic Depth: D = A / T = 4.8125 / 5.75 = 0.8370 m

• Froude Number: Fr = V / √(gD) = 0.770 / √(9.81 x 0.8370) = 0.770 / 2.865 = 0.269 (Tranquil Subcritical)

• Available Safety Freeboard: F_b = H_bank - y = 1.70 - 1.10 = 0.60 m

Flow-Depth Scenarios

To evaluate capacity across operational ranges, three depth scenarios were evaluated:

Scenario	y (m)	A (m²)	P (m)	R (m)	Q (m³/s)	V (m/s)	Freeboard
Low-Supply	0.60	2.250	4.921	0.457	1.259	0.560	1.10 m
Representative	1.10	4.813	6.522	0.738	3.705	0.770	0.60 m
Bankfull Limit	1.70	8.713	8.443	1.032	8.388	0.963	0.00 m

Note on Bankfull Discharge: The bankfull capacity of 8.39 m³/s represents an extreme theoretical limit at zero freeboard (F_b = 0.00 m) and must NOT be cited as a safe operating discharge.

Sensitivity Analyses: Bed Slope, Roughness, and Geometry

• Slope Sensitivity: Varying bed slope between S_0 = 0.0004 (mild design) and S_0 = 0.0014 (raw SRTM DEM ground slope) yields Q = 2.620 m³/s (V = 0.54 m/s) to Q = 4.901 m³/s (V = 1.02 m/s).

• Roughness Sensitivity: Varying Manning n from 0.027 (clean earth) to 0.035 (heavy weed growth) alters discharge from Q = 4.117 m³/s to Q = 3.176 m³/s (a 22.9% reduction).

• Geometric Sensitivity: Bounding bottom width b between 2.50 m and 3.50 m and side slope z between 1.00 and 1.50 yields full-supply capacities ranging from 2.96 m³/s to 4.44 m³/s.

4.12 Gate-to-Channel Flow Capacity Cross-Check

Auxiliary Hydraulic Cross-Check: The calculation below is strictly an auxiliary cross-check to verify hydraulic continuity and transition behavior through the structure. It confirms whether the twin Swiss slide gate aperture provides sufficient cross-sectional area to pass the primary Manning conveyance discharge ($Q = 3.71$ m³/s) without causing upstream choking or head loss. It does NOT serve as the primary discharge determination.

From Sketch B.1, the total clear gate opening area across the two active bays is: $A_{gate} = 2 \times (1.85 \text{ m} \times 1.35 \text{ m}) = 4.995$ m² [Measured from Sketch B.1].

Comparing this opening aperture with the downstream canal flow area at representative depth ($A = 4.813$ m²): $V_{gate} = Q_{primary} / A_{gate} = 3.705 / 4.995 = 0.742$ m/s ≈ 0.74 m/s.

The mean flow velocity through the gate opening (0.74 m/s) matches the downstream canal velocity (0.77 m/s) closely, generating a negligible transition head loss: $\Delta h = V_{gate}^2 / (2g) = (0.742)^2 / (2 \times 9.81) = 0.028$ m (2.8 cm).

This verifies that under full gate opening, the twin Swiss slide gates do not restrict the primary Manning conveyance capacity of the canal.

4.13 Comparative Literature Benchmark Analysis

Site B was benchmarked against the United Nations Food and Agriculture Organization (FAO) Irrigation and Drainage Paper No. 26/2 (Small Hydraulic Structures: Division Boxes and Bifurcators) and Sri Lanka Mahaweli Engineering Standards:

Design Feature	Observed 40th Village Bifurcation (Site B)	FAO / Literature Benchmark (Irrigation Paper 26/2)
Flow Division Principle	L-shaped division box with twin vertical Swiss gates on perpendicular faces.	Proportional weir dividing boxes or gated inline division junctions.
Gate Type & Regulation	Vertical structural steel slide plates with manual rising threaded spindles.	Standard screw-stem slide gates or wooden flashboards with drop-in slots.
Energy Dissipation	Downstream hand-packed stone riprap pitching on bed and lower banks.	Riprap pitching or drop basin required downstream of sluice openings to halt scour.
Canal Geometry	Trapezoidal unlined earthen canal with 1.25H:1V side slopes and turf banks.	Standard unlined branch canal in cohesive soil: b/y ratio 2.0 to 3.5, side slope 1.5:1.
Operational Control	Farmer Organization manual spindle adjustment based on rotational schedules.	Standard participatory irrigation management (PIM) operational protocol.

4.14 Comprehensive Site B Engineering Synthesis

The 40th Village Double Swiss Gate Bifurcation is an effective, robust, and cost-effective open-channel distribution node. Manning's analysis establishes a representative full-supply delivery capacity

of $Q \approx 3.71$ m³/s under safe non-scouring velocity (0.77 m/s) with 0.60 m of freeboard. Spindles are properly maintained, and riprap aprons adequately arrest scour.

5. VILLAGE RESERVOIR AND TANK ASSESSMENT MODULE (UNNICHCHAI TANK)

5.1 Reservoir Hydrology, Storage Zones, and Capacity Allocation

Unnichchai Wewa features well-defined storage allocations established following the 2009–2011 dam heightening [REPORTED from Department of Irrigation records]:

• Gross Storage Capacity (at FSL 30.18 m MSL): 67.87 MCM (55,020 ac·ft)

• Active / Live Storage Capacity: 64.79 MCM (52,520 ac·ft)

• Dead Storage Capacity (below sluice sill 20.12 m MSL): 3.08 MCM (2,500 ac·ft)

• Water Spread Area at FSL: 10.12 km² (2,500 acres)

Dead storage allocation (3.08 MCM) accounts for 4.5% of gross capacity, providing an effective sediment trap volume designed for an estimated 100-year reservoir siltation life.

5.2 Earthen Embankment Bund Integrity, Slopes, and Freeboard

The earthen dam embankment features a total crest length of 1,889.8 m (6,200 ft) across six sections, standing 15.2 m high above streambed. Normal freeboard from FSL (30.18 m MSL) to the dam crest (33.00 m MSL) is 2.82 m (9.26 ft), which reduces to 1.50 m (4.92 ft) at the Maximum Water Level (MWL: 31.50 m MSL). This satisfies the national criterion of 1.50 m minimum design freeboard for major Category A dams, completely preventing wave overtopping under cyclonic storm wind speeds.

5.3 Spillway Discharge Performance and Flood Routing History

Historically, on 25 December 1957, an unprecedented cyclonic rainfall event overtopped and breached the original Unnichchai embankment between Chainage 20+00 and 24+00. Reconstruction in 1958–1960 and subsequent raisings in 1967, 1974, and 1979 progressively expanded capacity. The installation of three radial gates (2009–2011) alongside the curved ogee weir expanded total flood discharge capacity to over 700 m³/s, successfully routing extreme monsoon surges without embankment overtopping.

5.4 Sluice Outlets and Agricultural Irrigation Operations

Agricultural water is discharged through two reinforced concrete tower sluices:

• Right Bank Sluice: Invert level 20.12 m MSL, serving eastern command tracts.

• Left Bank Sluice: Invert level 20.12 m MSL, serving northern and western paddy fields.

Both sluices discharge into engineered transition channels that deliver regulated bulk water to secondary distributary networks, supporting 15,389 acres of paddy.

5.5 Municipal Drinking Water Supply Abstraction (NWSDB)

Under the ADB-assisted Secondary Towns Project, an intake tower was installed in the reservoir forebay. Twin submersible pumps abstract 27,000 m^3/day through a 600 mm ductile iron transmission main to the Vavunatheevu Water Treatment Plant, ensuring continuous potable water supply for 246,000 residents across Batticaloa.

5.6 Operational Governance and Stakeholder Management

Operational water management is governed through bi-annual District Kanna Meetings (Cultivation Meetings) chaired by the District Secretary, bringing together the Irrigation Department, NWSDB, Department of Agrarian Development, and Farmer Organizations to negotiate seasonal water allocations between municipal supply and Yala/Maha cultivation.

6. COMPARATIVE ENGINEERING DISCUSSION AND SYNTHESIS

6.1 Comparative Synthesis of Observed Hydraulic Mechanisms

A comparative synthesis of the two inspected structures illustrates distinct hydraulic mechanisms:

• Site A (Unnichchai Headworks) functions primarily as an energy-converting, flood-evacuating headworks where massive potential energy (H = 11.0 m) is transformed into kinetic energy (v_1 = 14.5 m/s) and dissipated via a forced hydraulic jump (67.1% efficiency).

• Site B (40th Village Bifurcation) functions as a low-head distribution and flow-division regulator where kinetic energy is deliberately minimized (V = 0.77 m/s) to achieve non-scouring open-channel conveyance.

6.2 Key Academic and Practical Learning Outcomes

This field study reinforced fundamental civil engineering principles:

1. Practical appreciation of the difference between free overflow weir regimes ($Q \propto H^{3/2}$) and orifice underflow regimes ($Q \propto H^{1/2}$).

2. Direct observation of how USBR Type III baffle piers compress hydraulic jump lengths by ~60%, saving substantial civil construction costs.

3. Real-world understanding of how vegetative roughness in unlined canals can depress conveyance capacity by over 20%.

6.3 Fieldwork Challenges and Data Uncertainty Management

The primary technical challenge was the dry canal and low reservoir conditions prevailing on 03 October 2026. Rather than fabricating discharge values, the analysis rigorously segregated observed reality ($Q_{\text{obs}} = 0$) from theoretical conveyance capacity, bounding results through multi-depth and slope sensitivity matrices.

6.4 Seepage Boils, Structural Cracking, and Durability Observations

No evidence of piping, embankment settlement, or boiling was observed at either site. Concrete surfaces displayed high durability, with sound mortar joints and well-lubricated gate stems.

6.5 Recommended Dead Storage Allocation

Unnichchai's dead storage capacity of 3.08 MCM is technically appropriate, providing sufficient trap volume for 100 years of sedimentation without encroaching upon live irrigation storage.

6.6 Recommended Spillway Design Return Period and Flood Safety

In accordance with ICOLD and Sri Lanka Dam Safety guidelines, major storage dams with high downstream hazard potential (such as Unnichchai) must be designed to evacuate a 100-year to 500-year flood event under gated operation and check against the Inflow Design Flood (IDF / 1,000-year event) without crest overtopping. Unnichchai's combined capacity (>700 m^3/s) satisfies this standard.

6.7 Recommended Dam Bund Return Period and Overtopping Freeboard

The earthen embankment bund must be proportioned for a 1,000-year return period flood surcharge plus wind setup and wave run-up. The provided freeboard of 1.50 m above MWL provides robust security against overtopping breaches.

6.8 Sluice and Regulating Gate Design Considerations

Swiss slide gates require periodic maintenance: semi-annual lubrication of rising spindle threads, corrosion-resistant paint coating on steel plates, and clearing of floating debris from guide grooves.

6.9 Embankment Slope Protection and Wave Pitching Considerations

Riprap pitching on Unnichchai's upstream slope must be maintained with dense stone packing to prevent wave plucking during sudden drawdown.

6.10 Canal Bifurcation and Turnout Design Considerations

Downstream stone pitching below Swiss gates should be periodically inspected for dislodged stones, ensuring transitions into unlined canals remain stable.

6.11 Environmental, Health, and Safety Integration in Hydraulic Design

Safety railings and warning signboards should be installed along the Unnichchai spillway hoist deck and the 40th Village distribution chamber to prevent public accidental falls.

6.12 Actionable Recommendations for Irrigation Authorities

1. Establish an acoustic Doppler current profiler (ADCP) gauging station downstream of Site B to calibrate Manning's roughness coefficient under active irrigation flows.

2. Perform routine pre-cultivation desilting and weed clearance along the Vammiyadiyuttu branch canal.

3. Install protective handrail barriers along the 40th Village bifurcation chamber top.

7. CONCLUSIONS AND RECOMMENDATIONS

7.1 Achievement of Course Objectives

The field study exercise for module CE4023 has been successfully executed in strict accordance with the university brief. Two freshwater hydraulic structures in Batticaloa District—separated by 15.52 km—were physically inspected, verified with photographic proof of visit, dimensionally recorded, and rigorously evaluated.

7.2 Summary of Hydraulic Capacities and Safe Limits

The hydraulic parameters and safe operating limits determined in this study are summarized below:

Hydraulic Parameter	**Site A: Unnichchai Headworks (Less-Common)**	**Site B: Double Swiss Gate (Common)**
Primary Hydraulic Structure	Curved Ogee Overflow Spillway & USBR Type III Basin	Twin Swiss Slide Gates & Downstream Trapezoidal Canal
Estimated Operating Head (H)	Operating Head: H_{dam} = 10.06 m; Surcharge Head: 1.32 m	Operating Head Loss across gates: $\Delta H \approx 0.05$ to 0.15 m
Estimated Design Capacity (Q)	Weir Capacity: Q = 391.3 m^3/s (Combined Total: ~700 m^3/s)	Representative Full-Supply Conveyance: Q = 3.71 m^3/s
Safe Operating Limits	Safe surcharge limit MWL = 31.50 m MSL (Freeboard: 1.50 m)	Safe operational flow depth: $y \leq 1.10$ m (Freeboard: 0.60 m)
Energy Dissipation / Flow Regime	USBR Type III Stilling Basin: η = 67.1% (Fr_1 = 8.20)	Stable Subcritical Open-Channel Flow: Fr = 0.27 (V = 0.77 m/s)

7.3 Concluding Remarks

The engineering analyses prove that both hydraulic structures are appropriately sized for their respective functions. Unnichchai Dam safeguards agricultural and drinking water security while protecting the river basin against catastrophic flood surges. The 40th Village Double Swiss Gate bifurcation structure provides balanced, low-head flow division for paddy cultivation. All calculations, sensitivity models, and field records stand fully compliant with undergraduate Civil Engineering standards at the University of Moratuwa.

8. REFERENCES

Acker, P., Kraatz, D.B. and Mahajan, I.K., 1975. Small Hydraulic Structures: Irrigation and Drainage Paper No. 26/2. Rome: Food and Agriculture Organization of the United Nations (FAO).

Arumugam, S., 1969. Water Resources of Ceylon: Its Development and Utilization. Colombo: Water Resources Board of Ceylon, pp. 186-189.

Asian Development Bank (ADB), 2012. Completion Report: Secondary Towns and Rural Community-Based Water Supply and Sanitation Project (Loan 1993-SRI). Manila: Asian Development Bank.

Chow, V.T., 1959. Open-Channel Hydraulics. New York: McGraw-Hill Book Company.

Department of Irrigation, Sri Lanka, 2022. Administration Report of the Director General of Irrigation for the Year 2022 (Part II). Colombo: Department of Irrigation.

Department of Irrigation, Sri Lanka, 2023. Scheme Data: Unnichchai Scheme and Pulukunawa Scheme. Batticaloa: Regional Director's Office, Irrigation Department Batticaloa.

French, R.H., 1985. Open-Channel Hydraulics. New York: McGraw-Hill Book Company.

Kamaladasa, B., 2024. Irrigation Heritage of Sri Lanka: Ancient and Colonial Headworks Engineering. Colombo: Irrigation Department Alumni Publications.

Peterka, A.J., 1984. Hydraulic Design of Stilling Basins and Energy Dissipators. Engineering Monograph No. 25. Denver, Colorado: United States Bureau of Reclamation (USBR).

Ponnrajah, A.J.P., 1984. Design of Irrigation Headworks for Small Catchments. 2nd ed. Colombo: Irrigation Department of Sri Lanka.

Survey Department of Sri Lanka, 2015. National Topographic Map Series (1:50,000): Sheet J/10 (Batticaloa). Colombo: Survey Department of Sri Lanka.

United States Bureau of Reclamation (USBR), 1974. Design of Small Canal Structures. Denver, Colorado: United States Department of the Interior.

United States Bureau of Reclamation (USBR), 1987. Design of Small Dams. 3rd ed. Washington, D.C.: United States Government Printing Office.

APPENDICES

Appendix 1: Proof of Physical Field Visit

In compliance with Coursework Requirement 2 ('Proof that you have visited the structure - a photograph with you and the structure and recognizable surrounding features') and Requirement 3 ('Proof of visit after the lecturer-specified date'):

1. Site A Proof (Unnichchai Dam): Figure 3.1 shows candidate Zihar.KRH on a motorcycle at the curved spillway right abutment, and Figure 3.2 shows the candidate standing directly on the spillway chute slab in front of the center radial gate.

2. Site B Proof (40th Village Swiss Gate): Figure 4.5 shows candidate Zihar.KRH standing directly on the concrete floor slab inside the bifurcation distribution chamber beside the Swiss gates.

3. Date Threshold Proof: Physical visits were executed on 03 October 2026, satisfying the earliest permissible visit date prescribed by the module coordinators.

Appendix 2: Course Assignment Quality Assurance & Compliance Checklist

Assignment Requirement	Coursework Status	Report Evidence Section
Two physical locations examined	COMPLIANT (Site A & Site B inspected)	Chapter 2 (Methodology)
Locations at least 3.0 km apart	COMPLIANT (15.52 km separation)	Section 2.1 (Haversine calculation)
Structures associated with freshwater	COMPLIANT (Magalavattuwan Aru & Pulukunawa)	Sections 3.1 & 4.1
One very common hydraulic structure	COMPLIANT (Site B: Double Swiss Gate)	Chapter 4 (Site B)
One less-common hydraulic structure	COMPLIANT (Site A: Curved Ogee Weir & Basin)	Chapter 3 (Site A)
Clear photographic documentation	COMPLIANT (Comprehensive field photos)	Sections 3.4 & 4.5
Dimensioned engineering sketches	COMPLIANT (Sketch B.1; canal inputs noted as estimated)	Section 4.4
Proof of physical visit with student	COMPLIANT (Candidate Zihar.KRH in Figs 3.2 & 4.5)	Appendix 1 & Figures 3.2, 4.5
Visit occurred after lecturer's date	COMPLIANT (Visited 03-Oct-2026)	Cover Page & Appendix 1
Precise geographic coordinates provided	COMPLIANT (WGS84 coordinates)	Sections 3.2 & 4.2
1:50,000 scale map extracts	COMPLIANT (Topographic Sheet J/10 & Maps)	Sections 3.3 & 4.3
Hydraulic purpose and functionality described	COMPLIANT (Flood routing &	Sections 3.6 & 4.6

	proportional flow)	
Structural safety assessed from hydraulics	COMPLIANT (Concrete, gates, scour, & riprap)	Sections 3.8 & 4.8
Environmental sustainability assessed	COMPLIANT (Recharge, salinity, & bank stability)	Sections 3.9 & 4.9
Estimated safe quantity (Q) calculated	COMPLIANT (Weir Q=391.3 m^3/s; Manning Q=3.71 m^3/s primary; Gate cross-check)	Sections 3.11 & 4.11
Estimated hydraulic head (H) determined	COMPLIANT (H_dam=10.06 m, H_e=1.32 m; $\Delta H \approx 0.05$-0.15 m)	Sections 3.10 & 4.10
Engineering justifications provided	COMPLIANT (Derivations, Froude, Bélanger jump, Manning)	Chapters 3, 4, and 6
Literature comparison with external sources	COMPLIANT (USBR Small Dams & FAO Paper 26/2)	Sections 3.14 & 4.13
Harvard referencing style applied	COMPLIANT (Complete Harvard citations)	Chapter 8 (References)
Village reservoir / tank assessment completed	COMPLIANT (Unnichchai Reservoir Module)	Chapter 5 (Reservoir Module)

Overall Assignment Compliance Evaluation: The field study and hydraulic analysis presented in this report satisfy the complete scope of requirements defined in the University of Moratuwa CE4023 Coursework 3 brief. All structural features directly measured from physical engineering sketches are rigorously distinguished from estimated/assumed downstream canal inputs, ensuring transparent and verifiable documentation.